Status of the EUSPARC proposal

Massimo.Ferrario on behalf of the EuSparc team





Report on the EUSPARC design study at LNF

(European Source for Plasma Accelerators and Radiation user Communities) <u>Massimo Ferrario@LNF INFN IT</u> on behalf of the SPARC_LAB - EUSPARC collaboration

Sptember 14, 2016

If the proposed SPARC_LAB upgrade, named EUSPARC and discussed in the following paragraphs, will be completed within the next 6 years, we believe it will be possible to strongly candidate LNF to host the EuPRAXIA European Facility.

In order to meet the EuPRAXIA requirements some important preparatory steps must be set up at LNF:

- Consolidating the existing infrastructure in order to qualify SPARC LAB with significant experimental results in the field of plasma accelerators and FEL.
- Consolidating in the very short term the existing expertise with staff positions for at least: 3 accelerator researchers (Plasma, Diagnostics and FEL Physics), 2 high power laser experts and 2 laser technicians.
- Investigating the availability of a large infrastructure at LNF or build a new experimental hall able to host the EUSPARC facility.
- Provide within one year a Conceptual Design Report with a scientifically exciting program for EUSPARC itself.

A number of significant improvements of the existing SPARC LAB facility are underway, mainly funded by MIUR via the EUROFEL_MIUR and "Premiale" contracts with an additional INFN contribution:

- FLAME maintenance and consolidation up to the nominal 300 TW power,
- · Injector upgrade for ultra-high brightness beams with a new RF gun,
- THz user beam line installation in the upper aisle,
- Thomson and External injection plasma beam lines final commissioning and operation,
- FEL short period undulator test and R&D on RF and optical alternatives including Quantum FEL studies.

In parallel to the facility consolidation actions listed above, a number of significant experiments are foreseen with the existing SPARC LAB facility, focused in achieving some of the fundamental requirements enabling the EuPRAXIA program. Within the next 5 years the SPARC LAB Work Program foresees:

FLAME – Self Injection experiments

Parametric study of the laser and plasma performances.

So for example by scanning the plasma density, electron energy has been varied from 50 MeV, to 175 MeV and up to 300 MeV.

Also by tuning plasma density, energy spread has been reduced from 100% to 20%.



Plasma Diagnostics



MachZender interferometer to measure the plasma density. Using this diagnostic we have shot to shot measurement of the density and the total

accelerating length.

Density has been varied (with gas pressure) from $\approx 5^*10^{18}$ to $\approx 2^*10^{19}$, and electron energy has varied consequently (has shown before).

PWFA – Particle Wake Field Accelerator



Experimental layout



Preliminary results





4 - EUSPARC SCIENTIFIC PROGRAM

The EUSPARC scientific program has three main directions:

- High gradient acceleration techniques for the next FEL and e+e- collider generations.
- Advanced radiation sources for photon science (FEL, Betatron, Compton, Channeling).
- Physics of high field interactions with matter.

The main required actions enabling the accomplishment of such a program are:

- The FLAME laser upgrade up to 1 PW
- The RF Linac upgrade up to 1 GeV



EUSPARC TDR Working Groups	
WG O – Project Management O.1 Executive summary	(M. Ferrario)
WG 1 – Electron beam design and optimization 1.1 Advanced High Brightness Photo-injector 1.2 HB Linac options, design and parameters 1.3 – Machine layout	(E. Chiadroni) (A. Gallo)
WG 2 – Laser design and optimization 2.1 FLAME upgrade 2.2 Advanced Laser systems	(M. P. Anania) (L. Gizzi)
WG 3 – <mark>Plasma Accelerator</mark> 3.1 PWFA beam line 3.2 LWFA beam line 3.3 Positron acceleration	(A. Cianchi) (A. R. Rossi)
WG 4 – FEL pilot applications 4.1 Plasma driven FEL 4.2 Advanced FEL schemes 4.3 FEL user applications	(F. Villa) (G. Dattoli) (M. Benfattoi)
WG 5 – Radiation sources and user beam lines 5.1 Advanced dielectric THz source 5.2 Compton source 5.3 User beam lines	(C. Vaccarezza)
WG 6 – Low Energy Particle Physics 6.1 Advanced positron sources 6.2 Fundamental physics experiments , LabAstro 6.3 Plasma driven photon collider WG 7 – Infrastructure	(A. Variola) (C. Gatti)
7.1 Civil Engineering and conventional plants 7.2 Control system 7.3 Radiation Safety	(U. Rotundo) (G. Di Pirro) (A. Esposito)

EUSPARC Civil Engineering





Equipped new building 130x35 m²

20. M€

Advanced RF Acceleration, X-band and Beyond

Sami G. Tantawi, Valery Dolgashev, Michael Fazio, Aaron Jensen, Mark Kemp, Zenghai Li, Jeff Neilson, and Collaborators



Summary- Solid Foundation for Extending to Higher Frequency and Gradient

- Gradients increased by factor of ~3, from 65 MV/m to > 170 MV/m
- Very high shunt impedance can improve RF to beam efficiency
- New Structure Topologies could go beyond 200 MV/m efficiently:
 - Pave the way for future high energy colliders
 - Revolutionize proton accelerators
 - Provide an economical driver for plasma wakefield accelerators
- New RF source designs improve efficiency and lower voltages:
 - Efficient modulators with short rise and fall times
 - Eliminate pulse compression for much higher system efficiency
 - Klystrons with no electromagnets and cost effective depressed collectors
- High efficiency allows NCRF operation beyond 10 KHz
- Many other applications light sources, medical linacs, ...

RF Undulator Example

Corrugated waveguide structure

Undulator Mechanical Structure

Electric Field Distribution

Corrugation Period=0.4254 λ Inner Radius=0.75 λ Outer radius= 1.01293 λ Corrugation Thickness= $\lambda/16$ Number of periods =98

RF λ = 26.24 mm (11.4 GHz)

Undulator Period = 13.93 mm Power required (for linearly polarized, K=1) = 48.8 MW Q0=94,000

High quality beam driven acceleration up to 1GeV @Eu_SPARC Stefano Romeo

(stefano.romeo@Inf.infn.it)

on behalf of SPARC_LAB collaboration

2016-07-12

Istituto Nazionale di Fisica Nucleare

Laboratori Nazionali di Frascati



Simulation parameters

> Plasma density $n \downarrow 0 = 2 \cdot 10 \uparrow 16$

- **Driver:**
 - Energy $\gamma = 500$
 - Charge *Q*=200*pC*
 - Length $\sigma \downarrow z = 1/k \downarrow p$
 - *α*=0.5
 - Emittance $\mathcal{E} \downarrow n = 10 \ mm \ mrad$
- Spot size $\sigma lr = \sqrt{4 \& 1/\gamma} \sqrt{2 \varepsilon ln} / k lp$
- Emittance $\mathcal{E} \downarrow n = 0.3 \ mm \ mrad$





• Charge Q=15pC

• Energy $\gamma = 500$

Witness:

• Length $\sigma \downarrow z = 3 \mu m$

Energy and energy spread







Envelope and emittance









1 GeV, 0.1 %, 0.5 um, 1kA

2.8 cm , k=2 , rho 10^-3 => 10 nm in 20 m und

Cooperation length ~ 2 um

Dedicated meeting at LNF on OCTOBER 3rd about parameter and possible test experiments (DESY, INFN et al.)



Energy=1GeV

$$\lambda_1 = \frac{\lambda_u}{2\gamma^2} \left(1 + \frac{K^2}{2} \right)$$







Saturation length

 ϵ_n =1. um





WP COMPTON SOURCES

C.VACCAREZZA



IN DETAIL:

With a 2.3 eV laser beam and:

• 75-740 MeV Linac \longrightarrow 2-19.5 MeV γ beam:

GDR (Giant Dipole Resonance)

• I.I GeV Linac \longrightarrow 45 MeV γ beam:

2nd harm. GDR effects (never observed up to now)

• 1.35 GeV Linac \longrightarrow 60 MeV γ beam:

Polarized Positron Source

by ICS polarized photons (P. Musumeci& L. Serafini provate comm., Omori NIM A 500,232, 2003)

I GEV e⁻ BEAM FOR EUSPARC (6 more C-band sections)



Laser-Plasma Astrophysics

Esperimenti di Astrofisica in Laboratorio utilizzando un laser di potenza (1 PW)

Scalando opportunamente i parametri fisici è possibile simulare e investigare fenomeni astrofisici come:

- Supernovae
- Resti di Supernova
- Astrophysical Jets (γray bursts)
- Origine dei raggi cosmici e meccanismi di accelerazione
- Produzione di antimateria (positroni) etc. etc.



Claudio Gatti





Laser-Plasma Astrophysics

Prima riunione su Astrofisica in Laboratorio l'8 Luglio (coinvolti: Anania, Bisesto, Cianchi, Filippi, Gatti, Gizzi, Marocchino).

Obiettivi gruppo di lavoro:

- Individuare possibili esperimenti laser-plasma (in particolare con connessioni con fisica INFN, almeno un caso forte)
- Individuare la comunità di riferimento
- Individuare richieste per laser e diagnostica

Piano di Lavoro:

- Ricerca in letteratura esperimenti in corso
- Individuare casi di interesse
- Organizzare una giornata di discussione e confronto con esperti del campo
- Scrivere un report per fine anno

EUSPARC CDR timetable and milestones

- CDR expected delivery: end of March 2017
- Regular monthly meeting with the WPs coordinators

Month		Oc	tober		November				December					Jan	uary		February2					Ma	rch		
WG-7 -Infrastructure																									
Civil Engineering and conventional plants	Define C	ivil Engi	neering				Ten	der ready		Tende	r open						Optimized layout				Chapter ready				
Radiation Safety	Preliminary evaluations			Beam Dumps												Optimized layout				Chapter ready					
Control System												_						Chape	t ready						
																					L'				
WG-1 Electron beam design and optimization																					'				
Advanced HB photoinjector design	Con	ventiona	l/Ctyogenie	c Gun	Beam dynamics simulations S band					Injecto	or fixed						Chapet ready				'				
HB Linac options, design and parameters	Invest	tigation (-X bands	options	Beam dyn. simulations C/X band				RF Linac frequency fixed				RF Por	very Syste	ems Optin	nisation		Chape	et ready		'				
Linac layout										Bea	m extrac	tiom lines	Lin	ac layout	Optimisa	tion		Chape	t ready		 '				
																					'				
WG-2 Laser design and optimizations																					<u> </u>				
FLAME upgrade 500 TW design			_						Up	graded Fl	AME lag	yout						Chape	et ready		 '				
Advanced Laser systems													Du	al Beam (onfigura	tion		Chape	t ready		 '				
																					 '				
WG- 3 – Plasma Accelerator																					<u> </u>	<u> </u>			
PWFA beam line									Beam dy	y <mark>namic</mark> s si	mulation	s PWFA		Beam Li	ae Layout	t	Chapet ready				 '				
LWFA beam line									Beam dy	y namic s si	mulation	s LWFA		Beam Li	ie Layout	t –		Chape	et ready		<u> </u>				
Positron acceleration test									Beam dy	namics sir	nulations	Positrons		Beam Li	ie Layout	t		Chape	et ready		 '				
																					L'				
WG-4 – FEL pilot applications																					<u> </u>				
Plasma driven FEL		Undula	or Option	s		Undulat	or Fixed			FEL sim	ulations		St	art to End	l simulati	ons		FEL	layout		Chapter ready				
Advanced FEL schemes									RF	Undulator	investig:	ation		Compact	Undulator	rs		Chape	et ready						
FEL user applications									FE	L users wi	thout pla	sina	FEL us	ers at 1-1	nın with	plasma		_			Chapter ready				
																					 '				
WG 5 – Radiation sources and user beam lines																					<u> </u>				
Advanced dielectric THz source																		Chape	et ready		 '	\vdash			
Compton source															Chapet ready		et ready		'	<u> </u>					
User beam lines																		Chape	t ready		'	\vdash			
																					 '				
WG 6 – Low Energy Particle Physics																					<u> </u>				
Advanced positron sources																	Chapet ready				'	L			
Fundamental physics experiments , Lab-Astro																	Chapet ready					L			
Plasma driven photon collider																		Chape	t ready		L				

EUSPARC GANTT CHART

1			201	16			201	17			201	18		2019					2.0	26			202	1	
2	Month	3	6	9	12	15	18	21	24	27	30	33	36	39	42	45	48	51	54	57	60	63	66	69	72
3		-							-							s									
4	SPARC LAB Consolidation																								
5	FLAME maintenance and consolidatio	n up to	300 TV	N		() () () () () () () () () () () () () (
6	LWFA staging tests at FLAME				(-											Ĩ							
2	Thomson beam line final commissioning	ng	2	()																	ŝ.				
8	Exin beam line final commissioning an	d oper	ration	î.								_	1												
9	LWFA with external injection	000048555			1		-								_				1						
10	LWFA staging tests with external inject	tion)	-								2				1		1					
11	RF injector upgrade															_			() (_					
12	THz user beam line upgrade						1																		
13	Plasma Lens	_				-																			
14	High quality Beam acceleration PWFA		2]
15	Beam transport to FEL																								
16.	Plasma driven FEL studies		8																1						
17	Advanced undulators studies																								
18	SPARC LAB users operation																				i 1.				
19			1								1							-							
20	EUSPARC												1												
21	Machine Conceptual Design Report					_																			
22	Machine Technical Design Report																								
23	New building design	_									_									-					
24	New building authorisation requests		6	2						_	-			-											<u> </u>
20	New building tender	_	5					-					-					-			-				
26	New building construction		5 1	(() () () () () () () () () ()								-												
27	FLAME upgrade tender		3											-											_
28:	FLAME upgrade installation													1				-			-				
29.	FLAME commissioning to 1 PW			<u> </u>									1												
30	FLAME installation in the new building	g	Û.																	-					
31	LINAC upgrade tender																	1			-				
32	LINAC RF tests																								
33	LINAC and SPARC LAB installation	n in the	c new bu	uilding																					
34			4			-		-				_	_												
35	EuPRAXIA	_	8				_										2 2				-				
36	Design Study								8								6 1								
37	Preparatory Phase												- 1								and the second s				



EUSPARC total costs estimate

New infrastructure	20. M€
FLAME upgrade to 1 PW and related beam line	9.5 M€
Beam energy upgrade ~1 GeV and related experiments	16. M€
Grand Total	45.5 M€

Cost estimate

Upgrade of the front-end (currently 0.5J) to higher energy (>1J), short <15 fs pulse	1.5
duration and high ns and ps contrast	
Upgrade of the existing main amplifier for beam 1 at $\approx 1 \text{ PW}$	3.5
Installation of a new amplifier for beam 2 at 0.2 PW	3.0
Upgrade (and relocation) of the new compressor for beam 1	0.75
Installation of a new compressor set-up for beam 2	0.5
New layout of the target area, including fully shielded ceiling and dual beam target chamber	0.25
Total	9.5 M€

Cost estimate

Beam energy upgrade ~1 GeV	10. M€
PWFA modules and diagnostics	1. M€
Short period undulator development	3. M€
Positron beam line	2. M€
Total	16. M€