





1st Workshop of ELAN INFN-LNF, Frascati, 4-6 May 2004

Operating experience on CTF3



R. Corsini

OUTLINE

- CTF3: why, how & when
- The preliminary phase: description and results
- CTF3 injector and linac: commissioning experience









DRIVE BEAM GENERATION: THE CLIC RF POWER SOURCE

















- Build a small-scale version of the CLIC RF power source, in order to demonstrate:
 - fully-loaded accelerator operation
 - electron beam pulse compression and frequency multiplication using RF deflectors
- Provide the 30 GHz RF power to test the CLIC accelerating structures and components at the nominal gradient and pulse length (150 MV/m for 130 ns).





CTF3 STAGES





- 2003 Injector + part of linac
- 2004 Linac + 30 GHz high-power test stand
- 2005 Delay Loop + SHB
- 2006 + New photo-injector, CR + CLEX







R. Corsini, A. Ferrari, L. Rinolfi, P. Royer, and F. Tecker, "Experimental results on electron beam combination and bunch frequency multiplication", Phys. Rev. ST Accel. Beams 7, 040101 (2004).















Transition from **positive to negative** momentum compaction **a**_c seen on streak camera images for different settings of one guad family. d√d I QFLg = 92.0 A ac>0 8 × $\alpha_c \cong 0$ I QFLa = 93.5 A I QFLa = 94.5 A ac < 0 Time

I mages taken during the tenth turn at a location with nonzero dispersion. The horizontal position x is dependent on momentum, so the time-momentum correlation becomes apparent.



XA

t



Combination factor 4

Streak camera images of the beam at different turns, illustrating the bunch combination process

(260 mm/ps scale)



Beam current circulating in the ring measured during combination with a beam current monitor





Streak camera image of beam time structure evolution





Intensity profile at 1st and 4th turn









CTF 3 during 2003 installation period

Main beam parameters

	Nominal	Achieved
I	3.5 A	5 A
$ au_{ m p}$	1.5 µs	1.5 µs
E	35 MeV	35 MeV
ε _{n,rms}	100 π mm mrad	~ 110 π mm mrad *
$ au_{b,rms}$	5 ps	4 - 6.5 ps *
	* Preliminary - for 3.5 A, 1.5 μs beam	



CTF3 COMMISSIONING 2003 - GUN & TESTS















SLAC LAL I NFN/LNF design, simulations, commiss. support PB1 & PB2, commiss. support commiss. support



















USING RF SIGNALS IN HIGH BEAM LOADING OPERATION





SICA Cavity during high power tests



RF signals / output coupler of structure ACS305 (TDS)



- Beam loading signal as a function of RF phase in two CTF3 structures
- Phase difference ACS305 -ACS330 (w.r.t. beam) ~ 1°













I (a.u.)



OK below 1 A - Problems at high current:

- parasitic em signals
- both negative and positive signals
- strange pulse shapes (in time)
- saturation problems











- Screens in spectrometers and along the linac
- OTR screens:
 100 μm thick aluminum or carbon foils
- Cameras: radiation hard (low sens.) or CCD (noise)
- Optical lines to streak camera
- Studies on OTR angular distribution, beam halo monitor ...





EMITTANCE MEASUREMENTS





- Several quadrupole scans made in different conditions
- Horizontal scans consistent Not all vertical scans consistent (resolution limit in screens ?)





<u>BUNCH LENGTH MEASUREMENTS</u>



Phase scan method

Energy spread is measured for different RF accelerating phases, and compared with expected values for gaussian longitudinal profile bunches







HIGH CURRENT OPERATION - BEAM DAMAGE 1





Sign of heating from beam in spectrometer vacuum chamber



The second state of the second s













Demonstration of drive beam generation

- Final drive beam parameters (35 A, 2.3 nC/bunch, 150 MeV, 140 ns, 1.4 μs initial pulse length)
- Down-scaled with respect to CLIC (150 A, 10 nC/bunch, 2 GeV, 130 ns, 100 µs initial pulse length) but close enough to test relevant physical effects and benchmark simulation tools
 N.B.: different scaling laws involved for different effects !

Need to demonstrate not only beam current and pulse length, but also:

Low losses along the complex, beam emittance preservation, efficiency, control of bunch length, current stability, energy stability, bunch phase stability

Generation of 30 GHz RF power with CLIC nominal parameters

- Needed to test RF components (accelerating structures demonstration, but not only...)
- Acquire experience in power production operation (switch on/off power from PETS, ...)

Proposed: Test Beam Line to assess transverse stability & beam control in DB Decelerator

- String of PETS (10-15), choose relevant drive beam parameters need several betatron wavelength
- Measurement of wake-fields in decelerator (with probe beam ?)
- Study of halo production, machine protection...









CHALLENGES – STABILITY IN TRANSVERSE DEFLECTORS





Transverse stability in combiner ring – effect of RF deflectors wake

- 1. Final position and angle of bunches (systematic no injection errors)
- 2. Phase space footprint of merged trains (systematic no injection errors)
- 3. Tune dependence of the position and angle magnification of injection errors







M W

Power mode test







CTF3 layout (July-August 2003)















QDA0605 QFB0610 QDA0615

CL.QDA0605-S

BPM0690















Two phase scans were performed measuring the beam energy spread with MTV440 in different conditions on August 5th (vidicom), and 15th (CCD camera). The minimum values of the measured energy spread were respectively 0.56 % and 0.87 %. The best fit to the calculated curves is obtained correcting these values with an "uncorrelated spread" of 0.45 % and 0.3 %, yielding respectively 0.33 % and 0.74 % for the corrected values.



Assuming 3 ps time jitter, 3 ps intrinsic resolution and 3 ps slit

contribution, the estimated bunch length would be ~ 6 ps





MTV500 carbon screen 2 A, 20 MeV fast time scale, accum.



Diagnostics: screens





MTV 165 – Vidicom phosphor screen Dark current (pulsing off)



Diagnostics: screens



MTV 500 – CCD camera carbon screen

quad scan of August 13th







Operational limit with PB1











August 13th 6 A from gun 1.5 μs

Analog signals from scope read-out



Beam loading I





<u>Full beam loading – compressed RF pulse</u> August 12th (3.5 A) <u>First CTF3 fully loaded operation – no RF compression</u> August 5th (~ 3 A)





Beam loading II



Beam Loading experiment

- P_MKS03 = 31 MW no pulse compression
- E = 20 MeV
- I_BPE125 = 2.2 A
- I_BPM402 = 2.06 A
- I_BPM502 = 1.73 A
- Evaluate RF power out of TDS structure with and without RF, using output signals, peak power measurements at MKSO3 output. Assumed 5% losses in waveguides plus attenuation in structure calculated with Erk's spreadsheet.



- Compare with calculations from Erk's spreadsheet:
 - With RF $P_{out} = 2 \text{ MW}$ for I = 1.8 A ($\Delta E = 13.26 \text{ MV}$) • Without RF $P_{out} = 4.7 \text{ MW}$ for I = 1.8 A ($\Delta E = -5.56 \text{ MV}$)







- Calculate energy gain needed in ACS305 and ACS330 in order to reach 20 MeV (taking into account 5% losses in waveguides)
- Calculate (Erk's spreadsheet) power needed in each structure
- Compare with experimental data

