Commissioning and First Results from the Photo Injector Test Facility at DESY Zeuthen (PITZ)

- introduction
- rf measurements
- dark current
- measurements with beam

F. Stephan (DESY Zeuthen) for the PITZ Collaboration, ICFA Workshop @ Sardinia, Italy, July 1<sup>st</sup> – 5<sup>th</sup>, 2002

The Photo Injector Test Facility at DESY Zeuthen (PITZ) Goals:

• test facility for FELs and future LCs:

 $\Rightarrow$  very small transverse emittance (1 mm mrad @ 1 nC)

 $\Rightarrow$  stable production of short bunches with small energy spread

- extensive R&D on photo injectors in parallel to TTF operation
- compare detailed experimental results with simulations:
  ⇒ benchmark theoretical understanding of photo injectors
- test rf guns for subsequent operation at TTF-FEL
- test new developments (laser, cathodes, beam diagnostics)
- for TESLA: flat beams, polarized electrons

#### **Collaboration:**

BESSY, Berlin CAEP Mian Yang DESY, Hamburg and Zeuthen HEPI Tbilisi INFN Milano INR Troitsk INRNE Sofia Max-Born-Institute, Berlin TU Darmstadt, department TEMF

#### YERPHI Yerevan

#### **Current Layout**





#### • January 13<sup>th</sup>, 2002: first photo electrons



 $\Delta rf$  (laser- rf) = 5 kHz  $\Rightarrow$  automatic phase scan

## RF Conditioning in March 2002

duty cycle:

- rf pulse length: stable operation up to 400 μs
  (more needs adjustment of gun water cooling system, ongoing)
- rf pulse repetition rate: 5 Hz operation
- gradient at cathode: up to 34 MV/m, limit of old PS

(new PS is installed, now under commissioning)

#### DC measurements (preliminary results)





# Laser Parameters and Bunch Charge

Laser: (MBI, Berlin)



long. profile by streak camera:  $FWHM_z \approx 10 \, ps$ (still gaussian shape)

UV light at virtual cathode:

$$RMS_{x,y} = 0.65 mm$$

9,745697 ps



**Bunch Charges:** 

- during first run:  $Q_{bunch} \approx (5-30) pC$ 
  - after cathode exchange: up to 0.8 nC
    - serveral nC with better cathode handling



### Momentum Measurements



# Mean Momentum vs. RF Phase (preliminary)



### Calibration of Set Point voltage

maximum electron momentum vs. SP voltage:





possible explanation: RF amplitude changes during rf pulse

#### conclusions:

need to run with RF feedback (in preparation), measure momentum spread with low # of bunches

for **2**:

 $I_{main} = 190A$  $SP_{Voltage} = 27MV / m$  $Ch \arg e = 180 pC$  $SP_{Phase} = -50^{\circ}$ 

#### The new emittance measurement system at PITZ

• normalized transverse emittance:  $\epsilon_x^n = \beta \gamma \sqrt{\sigma_x^2 \sigma_{x'}^2 - c_{OV}^2(x, x')}$ 

emittance range: ~1-10 π mm mrad



#### Commissioning the emittance measurement system (very preliminary results)



parameters: SP = 32 MV/m I(main) = 166 A charge = 20 pC phase at optimum

- method 1: measure all parameters with beamlets
- method 2: measure beam size separately at position of slit mask
- method 3: beam size from M2, divergence as weighted av. from beamlets, correlation set zero

rm s values	method 1	method 2	m ethod 3
beam size	1.05	1.73	1.73
[m m ]			
d iv erg en ce	0.3676	0.3676	0.14
[m rad]			
covariance [m m .m rad]	-0.343	-0.343	
norm .em ittance	1.5	4.3	1.9
[mm.mrad]			

#### simulation result: 0.76 $\pi$ mm mrad

# Future plans @ PITZ

- upgrade rf system: better stability + higher output power (in autumn: 10 MW klystron)
- commission diagnostics (p&∆p, Q, BPM, EMSY, bunch length, long. phase space)
- until end of April 2003: gun should be fully characterized → use at TTF-FEL 2
- then: upgrade PITZ with a booster cavity
- 2004: measurements with higher beam energy (~ 40 MeV)

### Simulations with booster cavity (Ph. Piot)

TTF2 gun+sol. set-up with a booster



# Acknowledgements

for the current status of PITZ:

- strong support from technical groups, physics groups and administration at DESY (Hamburg and Zeuthen)

- people from cooperation partners: BESSY, CAEP Mian Yang, HEPI Tbilisi, INFN Milano, INR Troitsk, INRNE Sofia, Max-Born-Institute, TEMF@TUD, YERPHI Yerevan

- colleagues from DESY Hamburg: J.P. Carneiro, K. Flöttmann, Ph. Piot, J. Roßbach, S. Schreiber

- members of the Zeuthen PITZ group: J. Bähr, I. Bohnet, D. Lipka, A. Oppelt, T. Thon

# Summary

- photo injector test facility at DESY Zeuthen (PITZ) has taken first measurements with and without beam
- commissioning and upgrade is ongoing
- characterization of FEL gun is foreseen until spring 2003
- then upgrade facility with booster cavity