Koji Yoshimura KEK

June 28,2005 @MICE Collaboration Meeting

Outline

- What to do in step 2
- Preparation
- Time line

Phase 0 w/o B field, High p



Phase 0 Issues #1

- Light Yield
 - 3HF concentration
 - angular dependence
- Dead wire/ch distribution (efficiency)
- Cross talk
 - between adjacent fiber
 - between views
- position alignment
 - relative alignment between station
 - wire position within view

Phase 0 Issues #2

- Rate capability
 - 204 ch / view * 10 view = 2040 ch
 - if 5k ~ 10k events are required,
 - i.e., 1M~2M events in total for 1 configuration
 - and DAQ time is 1000~2000sec,
 - Then 1 kHz DAQ rate is necessary (cf. MICE 3 kHz/spill)

Phase 1 w/ B field, low p

Study tracking performance

– Defocused beam $\varphi300$

-0.2 GeV/c ~ 0.6 GeV/c

Phase 1 issues #1

- Precision p measurement
 - angular dependence (pt, roll)
 - momentum dependence 0.2 ~ 0.6 GeV/c
 - Defocused beam $\varphi 300$
 - 0.2 GeV/c ~ 0.6 GeV/c
 - Comparison with simulation

Phase 1 issues #2

- How to determine the reference
 momentum
 - Momentum bite of the pi2 beam line
 - officially 1% but should depend on the slit
 - can be estimated by using TOF as dr = 1

$$\frac{ap}{p} = \frac{1}{1-\beta^2} \frac{a\beta}{\beta} = \frac{1}{1-\beta^2} \frac{\Delta I O F}{T O F}$$

- T1 resolution : 58psec at 1 GeV/c, 55 psec at 2 GeV/c
- ΔTOF=58 psec for TOF=34 nsec
- dp/p = 2.8 %

Phase 1 issues #3

- How to determine the reference momentum?
 - TOF measurement
 - T1 σ=50 ps, T σ=60 ps ---> σ(TOF)=66 ps
 - p = 300 MeV/c ---> dp/p = 1.7 %
 - p = 400 MeV/c ---> dp/p = 2.9 %
 - Difficulties
 - Decay in flight ---> Aerogel Cerenkov Counter
 - Path length according to spiral motion in B field
 - Energy loss

Phase 2 w/ large emittance

Study of emittancemeasurement



Preparation/Status

• TOF

- Investigation of calibration scheme and TOF res
- Improve support structure
- Aerogel
 - LED calibration
- Magnet
 - Rotation mechanism
- VLPC
- SciFi Tracker
- DAQ

To be discussed in this meeting

Time line

- July
 - Proposal to be submitted
- August
 - All equipments will be shipped to KEK
 - VLPC and Scifi-tracker setup in PS hall
 - Possible meeting on VLPC and/or DAQ
- September
 - Cosmic-ray test
- September Octorber
 - Test beam
- December January
 - Test beam II