## SUPERCONDUCTIVE UNDULATORS/WIGGLERS STATUS-QUO AND FUTURE DEVELOPMENTS

## (THE ANKA SC UNDULATOR PROGRAM)

R. Rossmanith (ANKA) for the collaboration

T. Baumbach, A. Bernhard (University of Karlsruhe)
B. Kostka, M. Hagelstein (ANKA)
E. Steffens, M. Weisser (University of Erlangen-Nürnberg)
M. Kläser, M. Schneider (I TP, Research Center Karlsruhe)
D. Dölling, D. Krischel, A. Hobl, S. Kubsky (ACCEL I nstr. GmbH)

# MOTIVATION

- Higher field for given period length
- (or larger gap for same period length and field)
- (or shorter period length for same field)
- Electrical tunability (no mechanically moving parts)

Late 90's: beam test at Mainz cw microtron with an in-vacuum sc undulator



Period length 3.8 mm 100 periods



### What fields were (and can be) achieved?



## **Field Limitations**





Danger: magnetic forces try to move wires a quench

## Three critical points in the construction of a sc undulator

I.) Magnetic forces try to move wires a quench: 2 critical zones





Collimator system in front of undulator (example for ANKA)



Top view (completely closed)



#### b.) Resistive wall beam heating



Inner wall:

Cu or HTSC

 $R_{room temp}/R_{4K} = RRR$ -factor (typically 60 -100) <u>High temperature:</u> R defined by lattice vibrations and imperfections



**ANKA Undulator** 

100 periods, 14 mm period length, gap 5 or 8 mm, max. 1.5 T @ 5mm





Stretched wire field masuement

(integral measurements)

III. Field quality (phase error):

different to permanent magnet undulator only mechanical errors

Field measurements with Hall probes calibrated at 4.2 K (or 1.8 K)



Mechanical errors (can be compensated by classical shimming techniques)

a.) temperature effects (bi-metal)



## b.) Position errors of the individual building elements





First undulator equipped with electrical shimming will be EU project. ESRF undulator (ANKA – ELETTRA – MAXLAB - ESRF collaboration)

New project: SC undulator with electrically

Variable polarization

Example:

Blue vertical field

Red horizontal field





## Summary:

Achieved: field factor 2 higher than in-vacuum room temperature permanent magnet devices
Beam tests with single pass beams successful
Storage ring test very soon (next weeks)
Undulators with intelligent electrical shimming under construction (EU-Project)
Next generation with factor 3 higher field under way