


CGEM Meeting  
Laboratori Nazionali Frascati - Jan 29, 2014

CGEM-IT project update



*Gianluigi Cibinetto*  
on behalf of the Ferrara group



# Outline

---

- Status of layer 2 mechanical design
  - part I: closing on the construction tooling, cathode and GEM design
  - part II: opening the discussion on the anode design
  - part III: summary of other important ongoing issues (integration)
- Construction plan and schedule review
- 2014 construction budget review
- CDR status for the mechanical design (postponed to the afternoon session)

# Status of layer 2 mechanical design

---

## Part I: closing on the construction tooling, cathode and GEM design

- The layer 2 mechanical design has completed at executive drawing level (except for the anode).
- In particular we delivered drawings for:
  - molds and other construction tools
  - GEM and cathode foils drawings
  - Durostone supporting rings
- All the drawings have been validated by the Ferrara group:  
**waiting for another green light to go on with the orders.**
  - the durostone rings will be reviewed also by people from Bari




# Construction tooling

---

- Order placed at the end of 2013 to CECOM, the factory is waiting for the drawings.
- They need about three months to have the work done.
- This must be our **highest priority**: about one or two weeks.
- Then we will go to the factory to explain them the details of the drawings.

# Molds for layer 2 construction

## Cathode mold




- Each of the five detector skins (cathode + 3 GEMs + anode) is pre-assembled on an aluminum mold.
- Each skin has its own mold

Aluminum rings for correct positioning during assembly


Durostone rings for detector support

Aluminum ring for assembly



**Molds and aluminum ring design ready!**

# Molds for layer 2 construction






# GEM and cathode foils

---

- GEM and cathode foils drawings have been prepared and validated by Bertrand Mehl (the person designated by Rui de Oliveira for our GEM production).
- Our drawings have been converted to their CAD files and double-checked: that will be the procedure once we validated our final drawings.
- These drawings are needed also to modify the aluminum table that will be used for the foils gluing in Frascati.
- **Time for delivery?**




# GEM-I foil drawing



Here what is still missing is something to tell the manufacturer which side contains the HV microsectors.

# CERN drawings



can we say that  
we are going to reuse the  
same HV convention of  
Kloe and the same HV  
connectors.


# Durostone rings

---

- The durostone supporting rings will be ordered by Resarm factory in Belgium.
- The same of Kloe, no time to do further investigation.
- Drawings have been prepared.
- Preliminary offer requested, the price is a little higher w.r.t. Kloe, but they bought them almost four years ago.
  - About 12 keuro for a complete layer
  - About 2 months to complete the work



# Cathode ring





# What is missing

---

- Molds and tooling
  - validation
- GEM and cathode drawings
  - micro and macro-sectors placement
  - validation
- Durostone rings
  - validation
- We never checked the numbers given by Mingyi Dong in the presentation “Space available for CGEM installation” at the April 2013 workshop. I would be more comfortable doing a cross check.

# Anode design

# Motivation

---

- For a thousand of reasons it's of paramount importance to start the discussion on the anode design and implementation...
- ...even if we don't know yet many details.
- We already have several information to start the gross of the design.
  - Strip pitch, number of channels, number of boards, stereo angle, active area.
  - We have a guess about the stratigraphy and thickness.
  - Shortly we'll have a also an idea of the ASIC board dimensions.



# Anode design: main issues


---

1. About 3 mm will be the distance between the readout plane and the ground plane
    - need to assemble ourselves the readout and ground planes in a robust structure.
    - need to merge, at some point, the ground and the signals in a single connector.
  
  2. Lack of space in z direction
    - but a lot of unused space between the active area and the edge of the chamber.
- Not an easy task.


# Proposed stratigraphy

- This could be the layer configuration with a Compass-like readout plane at 3 mm from the ground.

~ 5 mm total thickness




# Proposed layout




# Layer 2 mechanical design


Assembly of the layer composed by a cathode, 3 GEM foils and the anode, each independently pre-assembled.



# The anode design



# The anode design




# Mechanical constraints and integration





# Construction plans, schedule and budget for 2014

# 2014 construction schedule



# Additional mechanical tests

---

... not included in the schedulee

- A new cathode prototype: this time full scale, using a Kloe mold.
- Anode prototype need to be assemble as well.

# Setup of the construction area

---



# To have it done we need:

---


- Second half of the Rohacell order (2.0 kE)
- Kapton roll (2.0 kE)
- Copper coated Kapton (3.0 kE)
- Durostone rings (12 kE) **should be part of the MAE 2014 assignment  
possibility to do a partial order now (just to  
start): ~3kE**
- Other minor but useful stuff (2-3 kE)

# Review of 2014 construction budget

	LNF (k€) (INFN+MAE)	LNF (k€) (CSN1)	FE (k€) (CSN1)	TO (k€) (CSN1)
Catodo e gems 2t			11	
Catodo e gems 3t			11	
Anodo 1t	13			
HV schede 1t	5			
Consumi gas e altro	8			
Lavori e materiali assemblaggio 1t	30			
Elettronica provvisoria 1t	15			
HV System (pw sup e distribuzione)	22			
Anodo 2t				10
Anodo 3t				10
Mandrini 2t			9(14)	
Accessori mandrini 2t			6(10)	
Rohacell 2t			2	
Consumo 2t			1	
Attrezzatura laboratorio			4	
Licenza 1y ANSIS Maxwell Edu			4,5	
I Fonderia ASIC (sj)				38
PCB per test ASIC				5
consumo ASIC				2
Licenza Cadence				0,5
2 PC per sviluppo ASIC				4
<b>Somma</b>		<b>80</b>	<b>22</b>	<b>30</b>
			<b>57,5(66.5)</b>	<b>49,5</b>

Thanks

# Schedule for detector construction



CDR approval by the BESIII collaboration →