



LABORATORI NAZIONALI DI FRASCATI

SIS – Pubblicazioni

LNF-96/027 (P)  
13 Giugno 1996

# RADIATION PROTECTION ASPECTS OF THE DECOMMISSIONING OF THE LINAC-ADONE STORAGE RING

M. Chiti and A. Esposito

INFN-Laboratori Nazionali di Frascati, Via E. Fermi 40, I-00044 Frascati (Rome), Italy

## Introduction

An  $e^+ e^-$  collider, christened DAΦNE (Double Anular  $\Phi$  factory for Nice Experiments), optimized for operation at a total energy of 1020 MeV, is under construction at the Frascati National Laboratories (LNF) of the National Institute of Nuclear Physics (INFN). The new machine will be placed into the existing buildings which in the past housed the Linac-Adone complex, which definitively ceased operation April 26th 1993 and was at once decommissioned.

The Linac-Adone complex has operated without stopping up to the 26th of April 1993 except for the ordinary maintenance periods.

It was composed by a Linac, capable of accelerating 100 mA of  $e^-$  beam peak current to 400 MeV and 1 mA of  $e^+$  beam peak current to 365 MeV, in operation since 1964, and by an  $e^+e^-$  storage ring capable of storing  $2 \times 10^{11}$  particles per beam at 1500 MeV, in operation since 1967.

PACS.: 87.50.NP; Radiation Protection

Submitted to

*Ninth International Congress of the International Radiation Protection Association*  
Vienna, Austria, 14 – 19 April, 1996

## **Radiation safety standard and criteria for unrestricted release adopted at LNF**

The objectives of radiation safety for the Linac-Adone decommissioning were:

- limitation of personal doses;
- control of radioactive materials either for reuse or for disposal;
- prevention of dispersion of radioactive material during handling and transportation to the final destination.

The limits for personal doses and radioactive material were taken from the recommendations of the Italian National Agency of Environment Protection (1) and from the law in force on the safety and health protection for workers and population against the danger of ionizing radiation field (2), as follows:

- the reference dose for people working in decommissioning areas was 15 mSv/y;
- a limit for unrestricted release for  $\beta$ - $\gamma$  emitters was set at 1 kBq/m<sup>2</sup> for surface contamination and 0.1 kBq/kg for mass activity.

## **Decommissioning organization and classification of materials**

In view of the rather low values of induced radioactivity no problems were expected as regards personal doses.

The biggest concern as regards radiation protection was the dispersion of radioactive materials outside the decommissioning area. A priori each machine item or component was considered radioactive until the contrary was proven.

At the exit of the Linac tunnel and the Adone storage ring area all materials were checked with the hand-held instruments: on non-radioactive materials a green adhesive tape was applied while the radioactive material was marked with a black trefoil on yellow background. Materials, whose radioactivity neither exceeded the clearance levels above mentioned nor made them a radioactive substances according to the law, were considered non-radioactive and were released completely free.

For instance all materials coming from control rooms, counting rooms or areas outside the accelerator's shielding or placed very far from primary or secondary beams were considered belonging to this category. Anyway, in case of doubt, samples were taken for gamma ray quantitative spectrometry measurements.

The radioactive materials which remained at LNF for reuse were stored in special areas at the disposal of every experimental group and finally those items intended for disposal were transported and stored into LNF radioactive waste area.

During the decommissioning two people of the radiation protection staff were permanently on the work site.

The personal doses for external radiation were monitored using pocket electronic dosimeters and a couple of TLD individual dosimeters (from an external company and from LNF service). Special clothes including overshoes were worn and in addition proper breathing masks were used during dusty operations in order to prevent any internal contamination. It needs to be stressed nevertheless that in the case of the LNF machine and in general in the case of high energy accelerators, the radiological risk for people involved in decommissioning was due practically only to the external radiation, being in fact negligible or absent surface contamination. The risk, very low actually, of internal contamination was connected to very particular and rare operations like sawing, cutting or cleaning.

Following the previous classification, all materials were divided into categories like "iron", "steel", "aluminium", "copper" etc., cut into pieces and compressed, if possible, to form easy to stock cubes.

Smaller metallic pieces (screws, connectors, pieces of cables, steel plates, etc.) were collected and put into baskets of about one cubic meter each. Special iron galvanized drums were used to store some cooling water coming from Linac beam dumps.

Each cube, drum or basket was marked with an adhesive tape with a radioactive material symbol on which the gamma dose rate was reported.

### Preliminary measurements

Following the shut down of the Linac-Adone complex, the Health Physics Service carried out many measurements to find out the amount of dose rate along e<sup>+</sup>e<sup>-</sup> beam lines, the specific activity in dust, in cooling water and in metallic components of the machine, in order to obtain useful information for planning the decommissioning itself.

Gamma dose rates, using CaF<sub>2</sub> TLD dosimeters (bulb dosimeter mod. 4040 by Harshaw) and a Victoreen ionization chamber mod. 450 P, were measured along e<sup>+</sup>e<sup>-</sup> beam lines at the distance of about 30 cm from the machine. The results obtained, shown in Figures 1, 2, 3, stress that the dose rate values are higher than the background only near the positron converter and the final part of the e<sup>-</sup> beam line before beam dump.

Liquid samples, collected from the primary cooling circuit of the machine supplied with aqueduct water and from the secondary circuit supplied with distilled or demineralized water show (Tab.I) an appreciable concentration of H-3, as expected, in cooling water of beam dumps.

Tabella I – Measured specific activity in water of Linac-Adone–Leale cooling circuits.

| Radionuclides                               | Co-58  | Co-60     | H-3       |
|---|--------|-----------|-----------|
| Cooling circuits                            | (Bq/l) | (Bq/l)    | (Bq/l)    |
| Linac-Adone primary cooling circuit         |        |           | 3.1±1.3   |
| Linac secondary cooling circuit (5350 l)    |        | 1.47±0.07 | 21.9±1.6  |
| Wiggler secondary cooling circuit (5500 l)  |        | 2.00±0.08 | 21.7±1.6  |
| Adone secondary cooling circuit (5900 l)    |        |           | 20.8±1.6  |
| Leale primary cooling circuit               |        |           | 18.8±1.7  |
| Leale secondary cooling circuit S2 (1500 l) |        |           | 30.8±1.8  |
| Leale secondary cooling circuit S3 (1000 l) |        |           | 7.4±1.6   |
| Linac beam dump 1 cooling circuit (2000 l)  |        | 0.27±0.03 | 3.5E04±43 |
| Linac beam dump 2 cooling circuit (6000 l)  |        | 1.38±0.06 | 3.4E04±42 |

In order to obtain useful information on possible contamination of areas involved in the decommissioning air and floor samples were taken: gamma spectrometric measurements show that no  $\gamma$  lines different from background were stressed in air samples and that only traces of Na-22, Mn-54, Co-57, Co-60, Ba-133, Cs-134, Cs-137, Eu-152, Eu-154, were found in dust samples. Further gamma ray spectrometries, performed in site at the location shown in Figure 4 and reported in Table II show clearly that residual radioactivity, was basically found near components in which beams were lost such as the positron converter, collimators, bending magnets or beam dumps.

Tabella II – In situ Linac-Adone-Leale gamma spectrometry.

| Radionuclides         | Co-56 | Co-57 | Co-58 | Co-60 | Cr-51 | Eu-152 | Na-22 | Mn-54 | Zn-65 |
|-----------------------|-------|-------|-------|-------|-------|--------|-------|-------|-------|
| Energy (keV)          | 847   | 122   | 810   | 1172  | 320   | 1408   | 1275  | 835   | 1115  |
| Measurement position  |       |       |       |       |       |        |       |       |       |
| Along the Linac       | (cps) | (cps) | (cps) | (cps) | (cps) | (cps)  | (cps) | (cps) | (cps) |
| Linac 1               |       | 81    |       | 9.7   |       |        |       | 0.73  |       |
| Linac 2               |       | 192   |       | 52    |       | 4.2    | 11    | 22.7  | 2.37  |
| Linac 3               |       |       |       | 1.85  |       |        |       |       |       |
| Linac 4               | 0.7   | 5.26  |       | 6.4   |       |        |       | 3.17  |       |
| Linac 5               | 2     | 19.7  |       | 5.9   |       |        |       | 4     |       |
| Along the Linac-Leale |       |       |       |       |       |        |       |       |       |
| Leale 1               |       |       |       |       |       |        |       |       |       |
| Leale 2               |       |       |       | 0.35  |       |        |       | 0.08  |       |
| Leale 3               |       |       |       | 7.4   |       | 8.5    |       | 4     |       |
| Leale 4               |       |       |       | 48    |       |        | 2.7   | 1.76  |       |
| Leale 5               |       | 28    |       | 132   |       | 0.43   | 7.6   | 34    |       |
| Leale 6               |       |       |       | 83    |       | 16     | 5.3   | 18    |       |
| Leale 7               |       |       |       | 99    |       | 14     | 39    | 14    |       |
| Leale 8               |       |       |       |       |       |        |       |       |       |
| Along the Linac-Adone |       |       |       |       |       |        |       |       |       |
| Transfer line 1       |       |       |       | 0.005 |       |        |       | 0.04  |       |
| Transfer line 2       |       | 12    |       | 0.06  |       |        |       | 0.62  |       |
| Transfer line 3       |       |       |       | 0.05  |       |        |       | 0.34  |       |
| Transfer line 4       |       |       |       | 0.03  |       |        |       | 0.36  |       |
| Transfer line 5       |       | 36    |       | 0.17  |       |        |       | 2     |       |
| Transfer line 6       |       |       |       | 0.034 |       |        |       | 0.16  |       |
| Transfer line 7       |       |       |       | 0.03  |       |        |       | 0.18  |       |
| Transfer line 8       |       | 60    |       | 0.54  |       |        |       | 11    |       |
| Transfer line 9       |       | 0.19  |       | 10    |       |        |       | 1.2   |       |
| Transfer line 10      |       | 43    |       | 0.2   |       |        |       | 8.7   |       |
| Transfer line 11      |       |       |       | 0.04  |       |        |       | 0.16  |       |
| Adone storage ring 1  | 0.46  | 19    | 1.1   | 0.4   | 4.6   | 0.22   |       | 9.4   | 0.09  |
| Adone storage ring 2  |       | 0.037 | 0.045 | 0.035 | 0.11  |        |       | 0.5   |       |
| Adone storage ring 3  | 0.04  | 2.2   | 0.06  |       | 0.2   |        |       |       |       |
| Adone storage ring 4  |       |       |       |       |       |        |       | 0.7   |       |
| Adone storage ring 5  |       |       |       | 0.031 |       |        |       |       |       |
| Adone storage ring 6  |       |       |       |       |       |        |       | 0.05  |       |
| Adone storage ring 7  |       |       |       |       |       |        |       |       |       |
| Adone storage ring 8  |       |       |       |       |       |        |       |       |       |
| Adone storage ring 9  |       |       |       |       |       |        |       |       |       |
| Adone storage ring 10 |       |       |       |       |       |        |       |       |       |

### Dismantling of the machine elements and final cleaning

On the basis of the results of the preliminary measurements the decommissioning program, the handling and transportation of materials began and were completed in 3 months without particular protections for people involved except the use of personal dosimeters and disposable dresses used in dusty operations.

During the dismantling the following instruments were used for in the field

measurements:

- two portable HpGe EG&G spectrometric systems;
- two environmental Reuter Stokes ionization chambers;
- a Victoreen 450 P ionization chamber;
- a Victoreen Frisker connected with a pancake probe;
- other useful monitors.

Two HpGe spectrometric systems in network with a 486 IBM PC were used for the quantitative analysis of samples.

Materials coming from Linac, including the 12 accelerator sections, the magnetic structures, the vacuum pipe line, the Linac-Adone transfer lines and 43 baskets, filled with remaining materials, were transported to the storage area without any quantitative measurements.

On the basis of the  $\gamma$  rate measurements it was clear that the most part of the materials had a concentration values higher than the clearance levels while the remaining ones not voluminous but very numerous, would have paralyzed uselessly all Health Physics Service  $\gamma$  ray spectrometric systems. More accurate measurements are foreseen for the future.

In Table III are reported, for instance, the results of the measurements carried out on the most radioactive parts of the accelerator.

Tabella III – Qualitative gamma-rays spectrometry on Linac components.

| Material                                       | Dose equivalent rate ( $\mu$ Gy/h) | 122 keV<br>Co-57<br>(cps) | 321 keV<br>Cr-51<br>(cps) | 810 keV<br>Co-58<br>(cps) | 835 keV<br>Mn-54<br>(cps) | 846 keV<br>Co-56<br>(cps) | 1275 keV<br>Na-22<br>(cps) | 1332 keV<br>Co-60<br>(cps) |
|--|------------------------------------|---------------------------|---------------------------|---------------------------|---------------------------|---------------------------|----------------------------|----------------------------|
| Linac section n°4 at contact                   | 1.5                                | 28                        | 4                         | 2                         | 12                        | 1                         |                            | 36                         |
| Linac section n°5 at 1 m of distance           | 750                                | 21                        |                           |                           | 39                        |                           | 1                          | 154                        |
| Linac section n°6 at contact                   | 1.7                                |                           |                           |                           | 0.8                       |                           |                            |                            |
| Linac section n°7 at 10 cm of distance         | 2                                  | 1.5                       |                           |                           | 1                         |                           |                            | 23                         |
| Linac section n°8 at 1 m of distance           | 14                                 |                           |                           |                           |                           | 0.08                      |                            | 20                         |
| Linac section n°9 at contact                   | 0.3                                | 3.5                       | 0.3                       | 0.2                       | 3                         |                           |                            | 18                         |
| Linac section n°10 at contact                  | 0.8                                | 13                        | 0.9                       |                           | 8                         |                           |                            | 58                         |
| Linac section n°11 at contact                  | 2                                  | 3                         |                           |                           | 1.6                       |                           |                            | 10                         |
| Linac section n°12                             | 1                                  | 59                        |                           | 3                         | 35                        | 1.                        |                            | 101                        |
| Bending magnet n°1 at contact                  | 11                                 | 12                        | 0.6                       | 0.2                       | 8                         | 0.4                       |                            | 7                          |
| Bending magnet n°2 at contact                  | 0.3                                | 1.7                       |                           |                           | 1.7                       |                           |                            | 1.6                        |
| Pulsed magnet at 50 cm of distance             | 30                                 | 0.6                       |                           |                           | 2                         |                           |                            | 54                         |
| positron converter target at 50 cm of distance | 230                                | 8                         |                           |                           | 4                         |                           | 1                          | 170                        |
| positron converter flange at 1 m of distance   | 500                                | 137                       |                           | 1.7                       | 127                       |                           | 197                        | 12                         |

Dose rate measurements carried out with a Reuter Stokes mod RSS112 during the cleaning of the Linac area from the remaining dust and reported in Figure 5, have shown appreciable values in the positron converter area with a maximum of 3  $\mu\text{Sv/h}$ .

A quantitative  $\gamma$  spectrometry measurement of a concrete sample, collected from a wall of the positron converter area, stressed the presence of Eu-152, Co-60, Cs-134, Eu-154 (Table IV), due to the concrete activation (n,  $\gamma$ ) of the Linac walls (3).

The decommissioning of the Adone area has caused many problems due to the big volumes and weights involved and to the very low value for unrestricted release. The Adone storage ring was formed of 12 identical sectors, each one composed by a straight section, a bending magnet, and a couple of quadrupoles for a total weight of about 35 ton/sector and the concrete shielding weighted about 800 tons. In situ  $\gamma$  spectrometry measurements were carried out on each part of the sectors in order to collect a sample from the most radioactive area. Anyway, the final destination of materials was determined on the basis of quantitative results.

All materials coming from Adone were released free except a few vacuum chamber.

Tabella IV – Residual radioactivity in the concrete walls.

| Radionuclides | Measured radioactivity (Bq/g) |
|---------------|-------------------------------|
| Be-7          | $0.020 \pm 0.002$             |
| Mn-54         | $0.0020 \pm 0.0003$           |
| Co-57         | $<0.0017$                     |
| Co-58         | $0.0045 \pm 0.0001$           |
| Co-60         | $0.420 \pm 0.001$             |
| Ba-133        | $0.0090 \pm 0.0005$           |
| Cs-134        | $0.160 \pm 0.005$             |
| Cs-137        | $0.003 \pm 0.0003$            |
| Eu-152        | $1.10 \pm 0.03$               |
| Eu-154        | $0.130 \pm 0.004$             |

Some results of the quantitative analysis, carried out on the most representative magnetic elements and vacuum chamber of the storage ring ( Figure 6), are reported in Table V. The measurements stress the presence of Mn-54 in the iron of a few bending magnets and Co-60 in the inox steel of a few vacuum chambers, where beams usually were lost (near injection devices).

Tabella V – Quantitative gamma-rays spectrometry on some representative Adone components.

| Radionuclide<br>mass activity         | Co-57<br>(Bq/g) | Co-60<br>(Bq/g)   | Mn-54<br>(Bq/g) |
|---------------------------------------|-----------------|-------------------|-----------------|
| Sample collected from                 |                 |                   |                 |
| Quadrupol 5                           |                 | 0.022± 0.002      |                 |
| Quadrupol 11                          |                 | 0.0092 ± 0.00103  | 0.0022 ± 0.0006 |
| Quadrupol 15                          |                 | 0.0072 ± 0.0007   |                 |
| Quadrupol 17                          |                 | 0.011 ± 0.001     |                 |
| Quadrupol 42                          |                 |                   | 0.0042 ± 0.0004 |
| Quadrupol 43                          |                 | 0.00085 ± 0.00007 | 0.022 ± 0.002   |
| Quadrupol 44                          |                 |                   | 0.033 ± 0.003   |
| Quadrupol 48                          |                 |                   | 0.0220 ± 0.0003 |
| Bending magnet 2                      |                 | 0.0080 ± 0.0007   |                 |
| Bending magnet 11                     |                 |                   | 0.0070 ± 0.0008 |
| vacuum chamber of<br>quadrupol 35     | 0.0017 ± 0.0003 | 0.0140 ± 0.0015   | 0.0033 ± 0.0008 |
| vacuum chamber of<br>quadrupol 37     | 0.11 ± 0.02     | 0.0650 ± 0.0063   | 0.11 ± 0.01     |
| vacuum chamber of<br>bending magnet 2 | 0.011 ± 0.001   | 0.017 ± 0.002     | 0.014 ± 0.002   |
| vacuum chamber of<br>quadrupol 42     | 1.50 ± 0.12     | 0.20 ± 0.02       | 1.20± 0.10      |
| vacuum chamber of<br>quadrupol 40     | 0.20 ± 0.02     | 0.092 ± 0.009     | 0.280 ± 0.025   |
| vacuum chamber of<br>quadrupol 43     | 4.70 ± 0.40     | 2.14 ± 0.30       | 9.70± 0.80      |

## Conclusion

The decommissioning of the whole Linac-Adone complex, including radiation protection measurements, has been completed in 6 months.

The continuous survey carried out by the Health Physics Service (1 physicist and two technicians) has obtained two important aims:

- 1) the movement of the activated material to the area of storage has been carried out avoiding any loss;
- 2) people involved in decommissioning have received doses, no higher than the background.

## References

1. Indirizzi di radioprotezione per l'allontanamento incondizionato dagli impianti nucleari di materiali solidi debolmente attivati e/o contaminati  
ENEA-DISP-CCPR documento L 85/01 del 26/5/96
2. Decreto del Presidente della Repubblica 13 febbraio 1964, n°185, Sicurezza degli impianti e protezione sanitaria dei lavoratori e delle popolazioni contro i pericoli delle radiazioni ionizzanti derivanti dall'impiego pacifico dell'energia nucleare. Supplemento ordinario alla Gazzetta Ufficiale n°95 del 16 aprile 1964
3. Itsumasa Urube, Katsuhei Kobayashi, Yoshiaki Fujita, Tadashi Tsujimoto and Jin Guangchuang, Health Physics Vol. 60, N° 4 (April), pp 587-591

### Dose equivalent rate from residual radioactivity

Measurements performed along the Linac at the shut-down using a Victoreen monitor model 450 P background 0.1  $\mu\text{Sv/h}$




Figure 1



# Dose equivalent rate from residual radioactivity

Measurements performed along the positron beam line at the shut-down using a CaF<sub>2</sub> TLD dosimeters




Figure 2

# Dose equivalent rate from residual radioactivity

Measurements performed along the electron beam line at the shut-down using a CaF<sub>2</sub> TLD dosimeters





Figure 3

# Linac-Adone-Leale Layout




Figure 4

### Dose equivalent rate from residual radioactivity ( $\mu\text{Sv/h}$ )

Measurements performed along the tunnel of the Linac at the end of the decommissioning, using an high pressure ion chamber Reuter Stokes model RSS112.




Figure 5

# Adone e<sup>+</sup> e<sup>-</sup> storage ring layout




Figure 6